BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92
EE/BTP/TEN/02/2012-13 D: 15.05.2012

SCHEDULE-B

Name of the work: Estimate for Providing to Cement Concrete roads Surrounding Kerosene bunk in Ward No. 10, (Doddabommasnadra) Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	301.52	KSRRB 300-2 : Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3 Page No. 150 / Item No. 19.2/ PWD SR 2012-13	Cum	Rs.81.00	Rupees Eighty One Only
2	291.56	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Page No. 12 /Item No. 4.3 PWD SR - 2012-13	Cum	Rs.3,884.76	Rupees Three Thousand Eight Hundred Eighty Four and Seventy Six Paise Only
3	790.80	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Page No.17 / Item No. 4.31 PWD SR - 2012-13	Sqm	Rs.244.08	Rupees Two Hundred Forty Four and Eight Paise Only
4	110.37	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.6 Page No. 13/ ITem No. 4.11 PWD SR - 2012-13	Cum	Rs.5,239.08	Rupees Five Thousand Two Hundred Thirty Nine and Eight Paise Only
5	55.19	KSRB 4.9.1: Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19/ Item No. 4.45 PWD SR 2012-13	Qntl	Rs.7,835.40	Rupees Seven Thousand Eight Hundred Thirty Five and Forty Paise Only

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
6	196.00	KSRRB M2600-3: Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification complete as per specifications, MORTH specification No. 2605, No. 248 Item No. 31.3 PWD SR 2012-13	M	Rs.132.84	Rupees One Hundred Thirty Two and Eighty Four Paise Only
7	187.77	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2, No. 12/ Item No. 4.5/ PWD SR 2012-13	Cum	Rs.4,937.76	Rupees Four Thousand Nine Hundred Thirty Seven and Seventy Six Paise Only
8	1877.70	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift No. 187 / Item No. 22.7/ PWD SR 2012-13	Sqm	Rs.86.40	Rupees Eighty Six and Forty Paise Only
9	301.52	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	Cum	Rs.72.71	Rupees Seventy Two and Seventy Paise Only

Signture of the Contractor

Technical Manager(TM-2)
KRIDL, Basaraham Zone, Bangalore

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92